

1. All construction methods shall conform to the Title V (310

NOTES

- 2. There are no known private or public wells within 100 any known surface water supplies within 400 feet of the proposed leaching area. The proposed leaching field is not within 100 feet of a wetland, nor is it within 200 supplies.

There are no abutter wells within 150 feet of the proposed leaching area.

The septic tank is located 89' from the edge of a wetland. The leaching area is located 101' from the edge of a

* Reference "Local variances" on this plan from leaching area to wetland and well located on the property.

wetland.

- 3. The existing septic tank and leaching pits shall be pumped and backfilled with clean fill after installing the new septic tank.
- No changes are to be made in the field without the approval of the Board of Health and the design engineer.
- The proposed leaching area is not designed for use with a
- (800) 344-7233. All system components to be covered by magnetic tape.
- be used as a property line survey.
- 8. Prior to construction, the contractor shall verify all and approved by the Boxford Board of Health.

All internal plumbing changes proposed for this septic system design shall be performed by a licensed MA plumber. Internal measurements performed by the design engineer indicate that the existing sewer invert elevation exiting the foundation (El. = 99.3) can be raised 3'. Prior to construction of the septic system, the proposed invert exiting the foundation (EL. = 101.25) shall be confirmed by a licensed MA plumber.

9. The delineaton of the wetland and wetland flags shown on this septic plan were performed by William Manuall (Soil

The approximate edge of the pond shown on this plan was extrapolated from MA GIS (Oliver).

10. In order to install the proposed septic system (septic tank 11 tress will need to be removed. All trees are located within 10 feet of the proposed septic tank and Presby Enviro-Septic System as shown on the plan view of this septic system

The closest proposed tree to be removed for the septic system installation is approximately 80 feet from the edge of wetland.

- 11. Contractor to install an inspection port using a 4" SCH 40 PVC pipe (perforation holes within the C-33 system sand of the leaching area) and removable PVC cover at grade. See Detal.
- 12. The contractor shall be responsible for obtaining a trench permit from the local municipality in which the work is being performed.
- 13. I certify that on 11/95 I have passed the soil evaluator examination approved by the Department of Environmental Protection and that the above analysis was performed by me consistent with the required training, expertise and experience described in 310 CMR 15.017.
- 14. The "Best Feasible Replacement System" consists of a field that is 37'L x 24.45'W, with the additional length of the leaching area to the north.
- 15. The "Conventional Leaching Field" consists of a field that is 37'L x 24.45'W, with the additional length of the leaching area to the north.

LEGEND		
Existing	Conto	ur
Proposed	Conto	ır
Test Pit		
Finished	Floor	Elev.
Basement	Floor	Elev.
Water Lir	ne	
Gas Line		

CMR 15.000) and the Boxford Board of Health Regulations.

feet/400 feet of the proposed leaching area, nor is there feet of a river front or known tributaries to surface water

garbage disposal. Remove any existing garbage disposal.

Contractor to notify Dig Safe 72 hours prior to construction

Property line information taken from Deed, Book 13128, Page 472, also reference Plan Book 129, Plan 58 (Lot 53). All wetland flags, wells, existing structures and topography were taken from a ground survey. The septic plan is not to

plumbing exiting the existing structure, as shown on this plan, can be connected to the new septic system. If any existing and/or proposed plumbing exiting the structure is found to be different then that shown on the approved septic system plan, the contractor shall notify the designer and corrections to the septic design will be made if applicable

Scientist) of Wetlands & Land Management, Inc. on April 23, 2021. The 100 foot wetland buffer on abutters property (65 Pye Brook Lane) is from an isolated wetland less the 5000

and Presby Enviro-Septic System) a minimum of 9, maximum of

TEST PIT DATA

Performed By: Daniel B. Johnson

Witnessed By: Kendall Longo

Date: May 13, 2021

TP-1 (EL. = 102.8)

(102.0)	Α,	0" - 10" 10YR3/2 Fine sandy loam		
(101.1)	Bw,	10" - 20" 10YR5/8 Gravely loamy sand		
(96.1)	С1,	20" - 80" 10YR4/4 Gravely M-C sand		
(92.8)	C2,	80" -120" 10YR5/4 Gravely loamy sand		
(92.8)		120" Assumed ESHWT (No Obs. Mottling)		
No Observed Groundwater				

TP-2 (EL. = 103.0)

(102.2)	A,			10YR3/2	Fine sandy loam	
(101.3)	Bw,	10" -	20"	10YR5/8	Gravely loamy sand	
(96.3)	C1,	20" -	80"	10YR4/4	Gravely M-C sand	
94.0)	C2,				Gravely loamy sand	
(94.0)	R,			Boulder/Le		
(94.0)		108″ A	Assun	ned ESHWT	(No Obs. Mottlng)	
No Observed Groundwater						

PERCOLATION TEST DATA

Date: May 13, 2021

Soil Class: Class I (0.74 G/SF)

Perc Rate: < 2 MPI (24"-42", TP-1)

SCHEDULE OF ELEVATIONS

Inv. Out Foundation 101.25 Inv. In Septic Tank 100.75 Inv. Out Septic Tank 100.50 Inv. In Distribution Box 100.42 Inv. Out Distribution Box 100.25 Inv. In Enviro-Septic Pipe (4" PVC) 100.08 Inv. Bottom Enviro-Septic Pipe Bottom of C-33 System Sand Assumed ESHWT (TP-2) Assumed ESHWT (TP-1)

SIZING OF ENVIRO-SEPTIC LEACHING SYSTEM

4 Bedrooms x 165 GPD/Bedroom = 660 GPD (Boxford BOH)

660 GPD / 0.74 G/SF = 891.89 SF

Using the Presby system allowance for up to 40% reduction in area, thus 891.89 SF x 0.60 (40% reduction) = 535.2 SF (400 SF min.)

99.50

99.00

94.0

92.8

Percolation Rate: < 2 MPI (Class I, 0.74 G/SF)

Slope of Proposed Leaching Bed: Level = 0%

* The following size requirements were taken from "Enviro-Septic Wastewater Treatment System Massachusetts Design and Installation Manual."

Table A: <2 MPI with 4 Bedrooms = 280 LF (min.)

Table B: System Slope at 0% with < 2 MPI = 1.5' (min.) spacing,

Table C: Use 20' long pipe at 280 LF with 1.5' (min.) spacing = 20.5' W (min.) and 14 lines,

Table D: 4 Bedrooms at < 2 MPI with Soil Class I = 400 SF (min.)

Proposed Leaching Bed: 22'L X 24.45'W with 14 lines at 20'L each with 1.65'W (actual) spacing (center to center), with 1.5 center to outside edge of sand bed = 537.9 SF

Proposed sand bed size: 22'L x 24.45'W = 537.9 SF (provided) > 400 SF (Presby min. required) and 535.2 SF (Boxford BOH).

VARIANCE: Local BOH Regulations

1. Request variance to reduce the offset from the edge of the proposed leaching area to the wetland, with a < 5 MPI perc rate from 150 feet to 101 feet, 201-9(E).

2. Request variance to reduce the offset from the edge of the proposed leaching area to the well servicing the property, with a < 5 MPI perc rate from 150 feet to 115 feet, 201-9(D).

98					
98]					
		SUBSURFA	CE SEWAGE DISPOSAL SY	STEM	
FFE		63 Pye Brook	Lane, Boxford (Map 30, Lo	ot 34)	
BFE		Date:5/18/21	Drawn By: Daniel B Johnson		
W		Prepared Robert Miller For: 63 Pye Brook Lane, Boxford, MA 01921			
G	SHEET I OF Z		TIC SEPTIC DESIGN, INC. Box 2406, S. Hamilton MA 01982	Dwg: J-2699	

