



TOWN OF BOXFORD

MASSACHUSETTS

01921

DEPARTMENT OF PUBLIC WORKS

7B Spofford Road Boxford, MA 01921

John C. Dold, P.E.
D.P.W. Superintendent

Phone: 978-352-6555
Fax: 978-352-5558

Permit No. NG-072220-23

Application Date: 5/27/2020

Start Date: 6/1/2020

Completion Date: within 1 month

PERMIT FOR STREET OPENING/RIGHT-OF-WAY CUT VALID FOR 30 CALENDAR DAYS ONLY

Application must be fully completed, including required plans, prior to consideration. Up to 20 business days may be required for processing

Name of Applicant: Tim Loiselle

Phone No: 781-674-6816

Company: Boston Gas dba National Grid

Emergency Phone: 781-674-6816

Address: 40 Sylvan Rd

PO Box or Street No. and Name

Waltham, MA 02451

City

State

Zip Code

Work Being Performed For: Boston Gas d/b/a National Grid

Location of Work: 22 Spofford Rd

Street No. and Name

Dig Safe Number: 20202117205

Surface Type: Asphalt

Length/Width/Type of Cut: 28' (L) x 2' (W) x 3' (D)

THE TOWN REQUIRES FORTY-EIGHT (48) HOURS NOTICE BE GIVEN TO THE OFFICE OF PUBLIC WORKS BEFORE THE COMMENCEMENT OF EXCAVATION, BACKFILL AND PLACEMENT OF OR PERMANENT PAVEMENT.

MUST CALL 48 HOURS IN ADVANCE

This permit is issued for the authorizing the above named applicant to work within:
Please Check Appropriate Boxes.

Public Right -of -Way Public Easement () Other _____
For the Purpose of: Installing Repairing Other _____
Gas Drainage () Conduit/Cable () Curb/Gutter ()

Remarks: install new gas service to 22 Spofford Rd

-working in street and street to house

The undersigned applicant being familiar with the requirements of the Town of Boxford Department of Public Works does hereby agree to perform all work in compliance with the regulations and specifications as set forth in the DTE 98-22 Standards.

Applicants Signature: TIM LOISELLE Date: 5/27/2020

Please Do Not Write Below This Line

Additional Requirements by D.P.W. (If Any): Attached

D.P.W. Superintendent: Chris Adkroft Conservation Director _____

Date: 7-29-20 Date: _____

Permit Fee: \$ _____

Street opening fee is \$50.00 per road

Board of Selectmen:

Charles Costello _____ Date: _____

Mary Ann Nay _____ Date: _____

Peter Perkins _____ Date: _____

Stephen Davis _____ Date: _____

Preston Galarneau _____ Date: _____



Gas Material View

22 Spofford Rd, BXF

Show search results for 22 Spo...



Potentially Contaminated Area - Contact Environmental Dept. Before

300ft

787,423.321 3,078,897.904 Feet



TOWN OF BOXFORD

Department of Public Works

7B Spofford Road
Boxford, MA 01921

www.town.boxford.ma.us

Office of the Superintendent

Tel: (978) 352-6555

Fax: (978) 352-5558

July 29, 2020

Standard Conditions for: NG-071320-23

The approval of the Town of Boxford is conditioned on the following:

1. A traffic management plan shall be submitted and approved by the town prior to work commencing.
2. All work under this permit shall be done in conformance with the Massachusetts Highway Department *Standard Specifications for Highways and Bridges* dated 1988, the *Supplemental Specifications* dated June 15, 2012, and the *Interim Supplemental Specifications*; the *2012 Construction Standard Details*, the *1990 Standard Drawings for Signs and Supports*; the *2009 Manual on Uniform Traffic Control Devices (MUTCD)* with *Massachusetts Amendments* and the *Standard Municipal Traffic Code*. More specifically, the backfill material shall meet the specifications of for:
 - a. Sand, M1.04.0
 - b. Gravel or Processed Gravel, M1.03.0, M1.03.1
3. The contractor shall install a permanent patch to the satisfaction of the inspector. Backfill material shall conform to the aforementioned specifications and shall be compacted in 6" lifts to a 95% Compaction. The overall pavement thickness shall match the existing pavement thickness or shall be a minimum of 2" Binder Course and 2" Top course, whichever is greater. In the event the pavement thickness is greater than 4", Binder Course shall be brought to within 2" of existing grade to ensure adequate top wearing course thickness is achieved.
4. The pavement shall be saw cut at the predetermined work limits. The contractor will tack the exposed asphalt faces at the saw cuts prior to paving.
5. Public shade tree(s) shall be double wrapped in a protective barrier (i.e 2x4, snow fence) in such a manner that it remains protected from damage for the duration of the work.

6. Any Catch Basins within 50' downstream of the limit of excavation shall have erosion control devices installed to prevent negative downstream impacts and/or the deposit of material within the town's drainage network.
7. Town of Boxford Street Opening Permits require the contractor to hire not only a Police Detail Officer, but also, a DPW Highway employee for all work hours when work is being performed in the Town's right-of-way, to inspect work performed. The charge for the DPW employee is the same as the Detail Officer per hour and will be scheduled a minimum of **48 hours** in advance with the DPW.
8. Further questions and additional requirements may be added per the order of the Boxford DPW Superintendent/Town Engineer, Chris Olbrot, (978) 352-6555.

Chris Olbrot, PE

Superintendent/ Town Engineer